

# LANDMARK SPOTLIGHT

## SINGLE TANK, MULTIPLE USE

### Hildebrand Road project for the San Antonio Water System

The San Antonio Water System (SAWS) gets maximum space utilization from their 2.0 million gallon Hildebrand Road tank, completed in 2008. One of four composite elevated tanks built by Landmark for SAWS, this structure combines potable water storage with an auxiliary system control room on the fully finished second floor, complete with meeting space, communications rooms, and an ADA-compliant rest room with shower facilities. A perimeter staircase and elevator provide easy access, while the ground level space incorporates a drive-in truck bay, plus open and locked storage areas. The site includes a back-up generator, pumping and chlorination equipment, and another existing storage tank devoted to recycled water.



*Landmark is pleased to have collaborated with SAWS on another efficient solution, as they stay out front in serving a steadily growing population.*



